

FINAL EVALUATION REPORT

(As Per Rule 35 of PP Rules, 2004)

1. NAME OF PROCURING AGENCY : PAKISTAN NATIONAL SHIPPING CORPORATION (PNSC),
 2. METHOD OF PROCUREMENT : SINGLE STAGE ONE ENVELOP PROCEDURE, AS PER PPR RULE 36(a) OF PPR 2004,
 3. TITLE OF PROCUREMENT : TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP,
 4. TENDER INQUIRY NO. : PRCD/CONS-REN/WS/PNSC/420
 5. PPRA REF. NO. (TSE) : N/A - **(Through PPRA EPADS SYSTEM)**
 6. DATE & TIME OF BID CLOSING : 21-01-2026 - (03:00 PM)
 7. DATE & TIME OF BID OPENING : 21-01-2026 - (03:30 PM)
 8. NO OF BIDS RECEIVED : FOUR (04)
 9. CRITERIA FOR BID EVALUATION : MOST ADVANTAGEOUS BID,
 10. DETAILS OF BID(S) EVALUATION : DETAIL IS TABULATE HEREUNDER;

NAME OF BIDDER	MARKS		EVALUATED COST OF PKR:	RULES/REGULATION/SBD*/POLICY/BASIS OF REJECTION/ACCEPTANCE AS PER RULE 35 OF PP RULES, 2004
	Technical	Financial		
M/s. MEHRAN Associates,	-	Lowest	<u>PKR: 10,146,845/-</u>	ACCEPTED AS PER PPRA RULE NO. 38, BEING MOST ADVANTAGEOUS BIDDER.
M/s. ISMAIL Engineering & Contractor,	-	2 nd Lowest	PKR: 11,769,375/-	SECOND (02) LOWEST BIDDER
M/s. VENTURE Builder,		3 rd Lowest	PKR: 15,915,890.75	THIRD (03) LOWEST BIDDER
M/s. CONTINENTAL Enterprises,	-	4 th Lowest	PKR: 16,873,079.25	FORTH (04) LOWEST BIDDER

MOST ADVANTAGEOUS BIDDER : M/S. MEHRAN ASSOCIATES,

11. Any other additional/supporting information, **SCANNED SIGNED BIDDERS COMPARATIVE STATEMENT IS ENCLOSED**

SIGNATURE:



ALI IMAM QADRI
General Manager (Procurement)

OFFICIAL STAMP:

STANDARD BIDDING DOCUMENTS (SBD).

2. Tender was opened on January 21st, 2026 at 03:30 PM in 16th Floor, Conference Room, Procurement Department, PNSC building in the presence of respective Tender Committee members and participated bidders.

3. In response thereto, following Four (04) firms/bidders have participated and submitted the proposal through EPADS Systems. Details are as under:

- i.) **M/S. CONTINENTAL Enterprises**, ii.) **M/S. ISMAIL Engineering & Contractor**, iii.) **M/S. VENTURE Builder**,
iv.) **M/S. MEHRAN Associates**,


4. After having scrutinized by the tender committee comprising of bids, Bidder Qualification and Evaluation Criteria as mentioned in the tender documents at the time of submission of their bids is placed opposite. Details are tabulated hereunder. Bidder's Comparative statement is prepared and is placed opposite for perusal.

Sr. No.	BIDDER QUALIFICATION / EVALUATION CRITERIA	M/s. Continental Enterprises	M/s. Ismail Engineering & Contractor	M/s. Venture Builder	M/s. Mehran Associates
i	Legal Status: The Bidder must be a legally registered for or company. (Copy of certificate of incorporation / Business Registration or Partnership Deed)	Submitted	Submitted	Submitted	Submitted
ii	PEC Registration: Valid registration with Pakistan Engineering Council (PEC) in a relevant category for civil works. (Valid PEC Registration Certificate).	Submitted	Submitted	Submitted	Submitted
iii	Tax Registration: Must be registered with FBR / SRB and appear on the Active Taxpayer list (ATL). (Copy of NTN Certificate, Sales Tax Registration, ATL verification Printout).	Submitted	Submitted	Submitted	Submitted
iv	Affidavit of Non-Blacklisting: The bidder must not be blacklisted or involved in any litigation with public or private sector entities. (Affidavit on Rs. 100 Stamp Paper duly notarized)/	Submitted	Submitted	Submitted	Submitted
v	Bid Security: Submission of bid security in an acceptable form. (Original pay order/Bank Guarantee/Insurance Guarantee as specified in BDS).	Submitted	Submitted	Submitted	Submitted
vi	Financial Feasibility: Demonstrated financial capability to execute a project. (Audited financial statements of last 3 years, Bank Statement or certificate showing sufficient financial resources).	Submitted	Submitted	Submitted	Submitted
vii	Relevant Experience: Minimum 3 years of relevant experience in similar construction/renovation works. (Copies of work orders, completion certificates, project list with client contact details)	Submitted	Submitted	Submitted	Submitted
viii	EPADS Compliance: Bid must be submitted electronically through EPADS in PDF format before the deadline.	YES	YES	YES	YES
ix.	General documentation Compliance: Submission of all required forms and documents as per ITB and BDS. (Letter of Technical Bid, Authority Letter, integrity Pact, Construction Schedule, Method of Work, Organizational Chart, List of Equipment, etc).	Submitted	Submitted	Submitted	Submitted
Total Bid Amount of PKR: (Including all Taxes)		16,873,079.25	11,769,375/-	15,915,890.75	10,146,845/-

5. As per the above Bidder Qualification/Evaluation Criteria and the Comparative Statement placed on record, **M/s. Mehran Associates** is the Most Advantageous Bidder with a quoted amount of **PKR: 10,146,845/-** and has fulfilled all qualification criteria as stipulated in the tender document.

6. In view of the above, the Tender Committee unanimously recommends that approval may kindly be accorded for the award of the Work Order to the Most Advantageous Bidder, **M/s. Mehran Associates**, for a total quoted amount of **PKR: 10,146,845/-** (including all applicable taxes) **for the Construction and Renovation of the Old Office Block at PNSC Workshop.**

7. Submitted for approval of Para-6 above please.



SIKANDER KHATTI
D.M (Workshop)
Member T/C



KASHIF KAMRAN KHAN
D.M (Finance)
Member T/C




CDR (R) ASADULLAH QURESHI
Manager (Workshop)
Member T/C



ALI IMAM QADRI
G.M (Procurement)
Chairman T/C

COMPARATIVE STATEMENT - TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP

Civil Works				M/S. CONTINENTAL Enterprises,		M/S. ISMAIL Engineering & Contractor		M/S. VENTURE Builders		M/S. MEHRAN Associates	
S. No.	Description	Unit	Qty	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount
1	Dismantling										
a.	ROOFING										
	Dismantling sheet roof and crane above 10 ft.in difficult position, including lifting with special scaffolding along live electric wire with machine underneath. Stripping and stacking slate or tiles from the truss roofing. And Dismantling wooden planks and battens	JOB RATE	1	149,500	149,500.00	150,000	150,000.00	100,000	100,000.00	85,000	85,000.00
b.	WOOD WORK										
	Removing door with chowkat. & Removing windows and sky lights with chowkat.	JOB RATE	1	74,750	74,750.00	50,000	50,000.00	60,000	60,000.00	25,000	25,000.00
c.	SCRAPING										
	White wash or color wash.Ordinary distemper, oil bound distemper.	JOB RATE	1	74,750	74,750.00	50,000	50,000.00	50,000	50,000.00	20,000	20,000.00
d.	ELECTRIC WIRING										
	Dismantling light, fan including casing and capping/strip open type, and making good damaged surface (building portion).	JOB RATE	1	74,750	74,750.00	50,000	50,000.00	30,000	30,000.00	25,000	25,000.00
2	EARTH WORK										
a	Supplying and fillingup to 3.5 ft. Selected approved earthing material obtained from site availability sources under floor etc. including breaking clods dressing, watering and consolidation by ramming in layers not exceeding 9 inches in depth to full compaction all as per drawing and approval of Engineer.	CFT	7,700	97.08	747,516.00	50	385,000.00	65	500,500.00	27	207,900.00
3	TERMITE TREATMENT										
a	Supply and applying termite treatment (killer treatment) using Biflex or approved equivalent with 10 years guarantee, (Termite proofing will be executed by manufacturer in three stages). (only plinth area shall be measured for payment)	SFT	2,225	60.47	134,545.75	30	66,750.00	40	89,000.00	25	55,625.00
4	GRANULAR MATERIAL										
a	Providing and laying compacted granular Material 3" thick packed with chips & spawls etc. including watering and compacting etc. complete in all respect.	SFT	2,225	134.38	298,995.50	55	122,375.00	150	333,750.00	50	111,250.00
	C.C. 1:4:8 LEAN ON FLOOR										
b	Providing and laying plain cement concrete 1:4:8 using crush stone up to 1-1/2" and down gauge in foundation including leveling,	CFT	600	523.25	313,950.00	250	150,000.00	199	119,400.00	300	180,000.00
5	PLAIN CEMENT CONCRETE FLOORING										
a	Providing and laying P.C.C. 1:2:4 platform for workshop including curing etc. complete.										
	a) 4" thick base	CFT	900	687.70	618,930.00	500	450,000.00	250	225,000.00	396	356,400.00
6	REINFORCEMENT										



COMPARATIVE STATEMENT - TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP

Civil Works				M/S. CONTINENTAL Enterprises,		M/S. ISMAIL Engineering & Contractor		M/S. VENTURE Builders		M/S. MEHRAN Associates	
S. No.	Description	Unit	Qty	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount
a	Providing & Laying Deformed steel reinforcement bars having minimum yield stress of minimum 60000 psi including the cost of straightening, cutting, bending, binding, wastages and such over laps as are not shown on the drawings placing in lintels of doors and windows complete in all respect.	KG	600	348.83	209,298.00	280	168,000.00	375	225,000.00	265	159,000.00
7	SOLID/HOLLOW BLOCK MASONARY						-		-		-
a	Providing and laying cement concrete solid machine made blocks having minimum yield stress of 1200 psi properly laid in coursed, as per drawings setting with 1:4 cement mortar, using screened fine sand including racking out jointing, curing scaffolding complete with all respect						-		-		-
	a) 6"x8"x12" solid block house outer wall and boundary wall 8" thick to be used following ASTM-C129.	CFT	2,875	269.10	773,662.50	90	258,750.00	199	572,125.00	225	646,875.00
8	PRECAST PLAIN SLAB FOR ROOFING						-		-		-
a	Providing and laying roof slab, Khassiparnalas in cement, sand mortar 1:2, 12" (300mm) outside width finished smooth with a floating coat of neat cement.	SFT	2,750	418.60	1,151,150.00	250	687,500.00	299	822,250.00	306	841,500.00
9	ROOF SCREED.						-		-		-
a	Providing and laying average 3" thick PCC 1:2:4 screed using graded screened bajri 3/4" and down gauge laid in proper gradient, including roof junction etc.	SFT	2,750	224.25	616,687.50	120	330,000.00	275	756,250.00	144	396,000.00
10	PAVER WORK IN GARAGE						-		-		-
a	60mm thick precast concrete grey paving blocks of size 8"x4" laid in approved pattern including 2" thick sand cushion, 4" thick CC 1:4:8 concrete base and preparation of base complete in all respect as shown on the drawings.	SFT	3,600	299	1,076,400.00	180	648,000.00	220	792,000.00	240	864,000.00
11	PORCELAIN TILE FLOOR						-		-		-
a	Providing and laying porcelain tiles (polished) of size 24"x24" approved quality, shade and colour of locally manufactured (Master, Shabbir or approved Equivalent) laid in approved pattern set in 1:4 cement sand mortar, setting of tiles in slurry of grey cement, filling the joints and washing the tiles with white cement slurry of matching colour, curing and cleaning etc. at any floor and height complete in all respect as shown on the drawings.	SFT	2,550	538.20	1,372,410.00	400	1,020,000.00	450	1,147,500.00	397	1,012,350.00
12	PORCELAIN TILE SKIRTING						-		-		-
a	Providing and laying glazed porcelain tiles skirting/dado of approved size, quality, shade and colour of locally manufactured (Shabbir, Master, or approved Equivalent) including border in wall laid in approved pattern over 1/2" thick rough plaster base in 1:4 cement sand mortar and setting of tiles in slurry of grey cement including filling the joints and washing the tiles with white cement slurry of matching colour, curing and cleaning etc. at any floor and height complete in all respect as shown on the drawings.	SFT	170	299	50,830.00	450	76,500.00	200	34,000.00	310	52,700.00
13	DOOR AND WINDOW						-		-		-
	METAL DOOR FRAME						-		-		-

Est. No. 2

COMPARATIVE STATEMENT - TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP

Civil Works				M/S. CONTINENTAL Enterprises,		M/S. ISMAIL Engineering & Contractor		M/S. VENTURE Builders		M/S. MEHRAN Associates	
S. No.	Description	Unit	Qty	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount
a	Providing & Laying 18 SWG, G.I. molded steel frames for doors including providing 1:2:4 concrete filling, providing and applying synthetic enamel paint of approved quality, color and shade over red oxide primer to each frame including fixing complete in all respect as shown the drawings.	RFT	240	747.50	179,400.00	900	216,000.00	165	39,600.00	348	83,520.00
	FLUSH DOOR						-		-		-
b	Providing & fixing Malaysian flush door shutter (approved factory made) (semi solid) 1-1/2" thick of approved quality and thickness including providing and applying polished of approved quality color and shades and cost of lipping, locks door stopper (metal), tower bolts and other iron mongery etc. complete in all respect as shown the drawings, specifications and as directed by the engineer at any floor height etc. comp.	SFT	260	1,495	388,700.00	750	195,000.00	499	129,740.00	817	212,420.00
	BEADING						-		-		-
c	Providing & fixing Soft wood beading / architraves of size 2"x1/2" as per design on all door frames with counter sunk headless nails including providing and applying polish, complete in all respect as shown on the drawings	RFT	240	897	215,280.00	240	57,600.00	140	33,600.00	127	30,480.00
14	ALUMINIUM WINDOW AND VENTILATORS						-		-		-
a	Providing and fixing bronze anodized aluminum glazed sliding window (deluxe model extruded section, 1.2mm thick) Lucky make or equivalent as approved including all hardware fittings 5mm thick Chinese tinted glass, aluminum fly proof shutter imported rubber gaskets etc. complete as per drawings, design and approved of Engineer at any floor and height complete.						-		-		-
	a) 1.6 mm section windows and ventilators.	SFT	190	1,704.30	323,817.00	1,200	228,000.00	2,150	408,500.00	1,725	327,750.00
15	PLASTERING						-		-		-
	INTERNAL PLASTER						-		-		-
a	Providing and applying 1/2" thick, 1:4 cement sand internal plaster smooth finished on block work, concrete surfaces including providing & fixing 18 gauge 12" wide expanded metal lath with min 6" overlap on RCC and masonry joints making groves, drips course, band, complete in all respect at any height any floor.						-		-		-
	b) Walls	SFT	7,500	149.50	1,121,250.00	75	562,500.00	150	1,125,000.00	75	562,500.00
	EXTERNAL PLASTER						-		-		-
b	Providing and applying 3/4 inch (20mm) thick cement plaster 1:4 to specified exterior surfaces including "PARKING WALL" providing and fixing 18 gauge, 12" wide expanded metal lath with min 6" overlap on RCC and masonry joints making groves, drips course, band, complete in all respect at any height any floor.	SFT	4,560	194.35	886,236.00	75	342,000.00	175	798,000.00	90	410,400.00
16	FALSE CEILING						-		-		-
a	Providing and fixing 2'x2' Dampa ceiling with channel, including framing, hanging supports, screws, aluminum tees etc. complete in all respect as shown on the drawing and as approved by the engineer.	SFT	2,225	269.10	598,747.50	500	1,112,500.00	400	890,000.00	165	367,125.00
17	PAINT WORK						-		-		-
	INTERNAL WALL PAINTING						-		-		-

COMPARATIVE STATEMENT - TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP

Civil Works				M/S. CONTINENTAL Enterprises,		M/S. ISMAIL Engineering & Contractor		M/S. VENTURE Builders		M/S. MEHRAN Associates	
S. No.	Description	Unit	Qty	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount
a	Providing and applying vinyl emulsion paint of approved make, quality, colour and shade including providing and applying wall sealer/primer, double filling, putty filling, rubbing with carborundum stone and final with sand paper complete in all respect up to entire satisfaction of the Engineer at any height at any level.	SFT	7,500	97.18	728,850.00	70	525,000.00	80	600,000.00	82	615,000.00
	EXTERNAL WALL PAINTING						-		-		-
b	Providing and applying vinyl emulsion paint of approved make, quality, colour and shade including providing and applying wall sealer/primer, double filling, putty filling, rubbing with carborundum stone and final with sand paper complete in all respect up to entire satisfaction of the Engineer at any height at any level.	SFT	3,600	127.08	457,488.00	70	252,000.00	90	324,000.00	83	298,800.00
	AERO PARKING SHADE						-		-		-
18	The parking shades structure are made from heavy duty galvanized pipes SWG 14 along corrugated sheet SWG 20 roofing including necessary overlaps, and GI hook bolts, nuts, screws washers and bitumen washers, etc. (excluding valleys and ridges, etc)	JOB RATE	1	1,046,500	1,046,500.00	350,000	350,000.00	675,000	675,000.00	200,000	200,000.00
Total Amount CIVIL WORK					13,684,393.75		8,503,475.00		10,880,215.00		8,146,595.00
SECTION – 01 ELECTRICAL SYSTEMS											
1	WIRING/WIRING ACCESSORIES										
1.1	Wiring of light point from switches to point with 2.5 sq.mm common neutral of 2.5 sq.mm. wires, including 20/25 mm dia concealed PVC conduit (Pakistan cable/Pak Arab/Steelex or equivalent)	NOS	16	5,980	95,680.00	7,500	120,000.00	5,500	88,000.00	5,000	80,000.00
1.2	Circuit wiring from DB to switches with 2x2.5 sq.mm PVC wires including any wiring between switch board to switch board, including 25mm dia pvc conduit (Pakistan cable/ Pak Arab/ Steelex or equivalent)	NOS	8	4,485	35,880.00	16,000	128,000.00	12,500	100,000.00	12,000	96,000.00
1.3	Wiring for Split type Air-Conditioning units from DB to 20A Switch Socket near indoor/outdoor units using 2 x 4 sq.mm. with 25mm dia PVC conduit concealed including wall, floor complete (Pakistan cable/Pak Arab/Steelex or equivalent)	NOS	4	2,990	11,960.00	16,500	66,000.00	16,000	64,000.00	12,000	48,000.00
1.4	Wall back boxes for use in wall conduit 3*3	NOS	50	598	29,900.00	80	4,000.00	200	10,000.00	100	5,000.00
1.5	Wall back boxes for use in wall conduit 3*6	NOS	10	747.50	7,475.00	120	1,200.00	299	2,990.00	140	1,400.00
2	SECTION – 02 Switch & Socket						-		-		-
	b) two gang switch Schneider clipsal or equivalent	NOS	2	1,644.50	3,289.00	500	1,000.00	2,000	4,000.00	650	1,300.00
	d) four gang switch Schneider clipsal or equivalent	NOS	1	1,794	1,794.00	500	500.00	3,000	3,000.00	750	750.00
	f) six gang switch Schneider clipsal or equivalent	NOS	7	2,093	14,651.00	1,000	7,000.00	4,000	28,000.00	1,000	7,000.00
	g) 13 Amp switches Schneider clipsal or equivalent	NOS	45	2,242.50	100,912.50	500	22,500.00	1,900	85,500.00	1,250	56,250.00
	i) RJ 45 switches	NOS	11	2,990	32,890.00	3,500	38,500.00	1,000	11,000.00	3,500	38,500.00
	j) RJ 11 switches	NOS	8	3,737.50	29,900.00	350	2,800.00	1,200	9,600.00	3,000	24,000.00
c	15 Amps switch socket Schneider clipsal or equivalent	NOS	12	2,242.50	26,910.00	500	6,000.00	2,100	25,200.00	800	9,600.00
d	20 Amps switch socket Schneider clipsal or equivalent	NOS	7	2,392.00	16,744.00	800	5,600.00	2,150	15,050.00	1,000	7,000.00
3	SECTION – 03 FIXTURES						-		-		-

COMPARATIVE STATEMENT - TENDER FOR CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK PNSC WORKSHOP

Civil Works				M/S. CONTINENTAL Enterprises,		M/S. ISMAIL Engineering & Contractor		M/S. VENTURE Builders		M/S. MEHRAN Associates	
S. No.	Description	Unit	Qty	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount	Unit Rate	Amount
	Supply and Installation for following type of approved LED lighting/fan fixture schedule installed on surface or on false ceiling with all allied accessories as per the satisfaction of the architect and consultant. brand Philips(Signify)/NVC/LED Vance by Osram or equivalent						-		-		-
3.1	Ceiling light-18 Watts (Min) brand Philips(Signify)/NVC/LED Vance by Osram or equivalent	NOS	95	1,196	113,620.00	400	38,000.00	2,550	242,250.00	550	52,250.00
3.2	External Wall Light-20 Watts (Min)	NOS	8	2,242.50	17,940.00	500	4,000.00	3,100	24,800.00	650	5,200.00
3.3	Wall Light-12 Watts (Min)	NOS	16	747.50	11,960.00	300	4,800.00	2,300	36,800.00	1,500	24,000.00
3.4	Circulator ceiling 24"x24" brand Voldam Fans/Pak Fans or equivalent	NOS	2	17,940	35,880.00	8,000	16,000.00	14,500	29,000.00	8,000	16,000.00
4	SECTION - 04 DISTRIBUTION BOARDS AND METERS						-		-		-
	Supply and Installation, testing and commissioning of following Distribution boards as shown on drawing made with 18 SWG sheet steel housing, flush in wall, surface type with approved color as specified circuit breakers and components as shown in drawings.	Job Rate	1	149,500	149,500.00	80,000	80,000.00	125,000	125,000.00	80,000	80,000.00
4.1	Providing, fixing, and testing of 1 ton inverter AC (GREE/HAIER/ORIENT) or equivalent	NOS	7	186,875	1,308,125.00	175,000	1,225,000.00	125,000	875,000.00	145,000	1,015,000.00
5	Section 5 CABLES & CABLE CONTAINMENTS						-		-		-
	Low Voltage Electric Power Conductors installation, termination and grade unarmored PVC/ PVC copper conductor cable in already installed PVC commissioning of following types 600/ 1000V conduit/cable tray as per specification.						-		-		-
5.1	Meter to DB 4x25 sq.mm four core	RFT	250	2,392	598,000.00	4,500	1,125,000.00	1,950	487,500.00	800	200,000.00
5.2	Supply, installation, testing and commissioning of PVC conduits with all bends, fittings, sockets etc. with all allied accessories complete in all respect.	RFT	5,500	74.75	411,125.00	30	165,000.00	120	660,000.00	40	220,000.00
6	SECTION - 6 CABLE TV SYSTEM, COMMUNICATION & NETWORKING SYSTEM						-		-		-
6.1	ONU device with all accessories etc. complete	NO.	1	44,850	44,850.00	150,000	150,000.00	10,000	10,000.00	4,000	4,000.00
6.2	Cat 6 for TV data etc.	NO.	1	44,850	44,850.00	45,000	45,000.00	10,000	10,000.00	6,000	6,000.00
6.3	Wi-Fi Router	NO.	1	44,850	44,850.00	10,000	10,000.00	13,000	13,000.00	3,000	3,000.00
Total Amount - Electrical System					3,188,685.50		3,265,900		2,959,690.00		2,000,250
ADD: Tax 15% SST					Included		Included		2,075,985.75		Included
Grand Total Amount of PKR:					16,873,079.25		11,769,375.00		15,915,890.75		10,146,845.00

As per comparative statement above, M/S. MEHRAN Associates is the Most Advantageous Bidder with the total quoted amount of **PKR: 10,146,845/-** (including all taxes), for FOR THE CONSTRUCTION AND RENOVATION OF OLD OFFICE BLOCK AT PNSC WORKSHOP.




SIKANDER KHATTI
Deputy Manager Workshop)
Member Tender Committee



KASHIF KAMRAN KHAN
Deputy Manager (Finance)
Member Tender Committee



CDR. (R) ASADULLAH QURESHI
Mnagaer (Workshop)
Member Tender Committee



ALI IMAM QADRI
General Manager (Procurement)
Chairman Tender Committee